


The angle with power





12/2017

PFEIFER SEIL- UND HEBETECHNIK GMBH

 DR.-KARL-LENZ-STRASSE 66

 87700 MEMMINGEN

 PHONE

 Technical support
 0 83 31-937-345

 Sales
 0 83 31-937-231

 FAX
 0 83 31-937-342

 E-MAIL
 export-bt@pfeifer.de

 INTERNET
 www.pfeifer.de

PFEIFER Bent Loop


Do precast slabs and angled elements have to be lifted safely and economically?

The economic limits are set very tightly when it comes to concrete elements. Nevertheless, there's no room for compromises on safety and use. Despite that, unsuitable and formally inadequate solutions are still often used in practice.



Self-made lifting anchors

Made of reinforcing steel or prestressing cables are not permissible without verifications and tests. They do not conform to the EC Machinery Directive.





PFEIFER Bent Loops help you to transport precast slabs and angled elements safely and cost-effectively

With a variety of possible applications, the new version of the PFEIFER Bent Loop enables the transport of the most diverse precast concrete elements - safely and in compliance with the directives.




Economical use

- · For flat elements and floor slab elements of all kinds
- · Round and rectangular
- For angled elements and L-shaped retaining walls

Technically versatile usability

- Straight pull
- Parallel shear pull
- Transversal shear pull for WS 0,8 to 2,4



3

The PFEIFER Bent Loop – strong thanks to performance, quality and economy



Tested for applications

With slabs and angled elements



Reinforcement


Ideally fastened via defined points



Optimised holding bracket

Enables the most diverse methods of fastening by:

- Welding on (WS 0,8 to 2,4)
- · Fixing with tying wire
- Fixing with cable ties, etc.



No additional reinforcement necessary

Conforms to the EC Machinery Directive

Taking into account the VDI/BV-BS Directive 6205



Made in Germany



PFEIFER Bent Loop for slabs and angled walls



The PFEIFER Bent Loop was developed to be used as a lifting anchor for lifting concrete elements. Regular stresses are Advantages: straight pull, parallel shear pull and transversal shear pull. The shape and the form of the holding bracket enable very simple installation and easy fixing to the reinforcement. Once the concrete has cured, a suitable suspension hook can be hooked into the protruding loop and the element can be transported safely.


PFEIFER

Bent Loop BS Anchor System

- · Safe lifting
- simple installation
- secure fastening in the reinforcement
- · no additional reinforcement
- · colour coding.


Material:

round strand rope, high strength, galvanized, Holding bracket, bare sheet steel



Type/Size	Ref. no.	b	d	I	h	Weight
		[mm]	[mm]	[mm]	[mm]	[kg/pc]
WS 0.8	05.023.083.205	~ 85	6	280	205	0.20
WS 1.6	05.023.163.205	~ 85	8	280	205	0.33
WS 2.4	05.023.243.285	~120	10	280	285	0.45

Product description



PFEIFER Bent Loops consist of a specially shaped holding bracket, a high-quality rope and an appropriately marked load capacity tag.

The holding bracket has two holes that can be used to fasten the loop to the reinforcement. The free ends are for anchoring in the concrete. After casting into the concrete, the loop protrudes above the concrete surface and can be used for attachment when lifting or transporting the precast concrete element.

Table 1: Colour coding

Type/Size	Colour			
WS 0.8	Pure white			
WS 1.6	Light pink			
WS 2.4	Anthracite grey			

Safety

In defining safety, it is assumed that the lifting anchors are used in precast elements manufactured in a factory with continuous monitoring. In accordance with VDI/BV-BS 6205, the working coefficients are as follows:

- Full section failure:
- Steel rope failure:
- Concrete failure:
- Dynamic factor (load side):

$\begin{array}{l} \gamma_{s} &= 3.0 \\ \gamma_{seil} &= 4.0 \\ \gamma_{c} &= 2.1 \\ \psi_{dyn} &= 1.3 \end{array}$

Intended use





Figure 6


Figure 7

Instructions for installation and use

Intended use



Dimensioning



., -,	0–30° [kN]	90° [kN]	reinforce- ment	reinforce- ment	structural element thickness	ü	sion e	distance from edge	distance from edge	distance s
	\geq 15 N/mm ²	$\geq 25 \text{ N/mm}^2$			a [mm]	[mm]	[mm]	c ₁ [mm]	с ₂ [mm]	[mm]
WS 0.8	6	7	R188 ²⁾	-	100	145	60	240	240	480
WS 0.8	8	7	2 x R188 ²⁾	-	120	120	85	240	240	480
WS 1.6	11	12	2 x R188 ²⁾	-	120	120	85	240	240	480
WS 2.4	14	14	2 x R188 ²⁾	-	150	170	115	240	240	480
WS 2.4	24	18	2 x R188 ²⁾	2 Ø 10mm ¹⁾	200	120	165	240	390	480




¹⁾ For the Bent Loop WS 2.4 with a permissible resistance of 24 kN an additional reinforcement 2ø 10 mm is to be installed in the upper reinforcement layer parallel to the anchor axis (fig. 15).

 $^{2)}$ across section: longitudinal direction = 188 mm²/m, transverse direction = 113 mm²/m

Instructions for installation and use

Dimensioning




Installation




Installation only by trained expert personnel:

- use only original PFEIFER Bent Loops
- adhere to all installation rules
- fasten the Bent Loop in such a way that its position cannot change
- compact the concrete carefully, paying attention to the built-in components



Fixing the loop




Fixing with a spot weld



The loop can be fastened by

- tie-wire
- spot weld
 cable tie.
- The holes should be used for fixing with cable ties and tie-wire.





A spot weld for fixing the loop may only be placed in the areas marked in figs. 24, 25 and 26. The areas marked in red in figs. 24, 25 and 26 may not be used for this.

PFEIFER Bent Loop for slabs



The PFEIFER Bent Loop was developed to be used as a lifting anchor for lifting concrete elements. Regular stresses are straight pull, parallel shear pull and transversal shear pull. The shape and the form of the holding bracket enable very simple installation and easy fixing to the reinforcement. Once the concrete has cured, a suitable suspension hook can be hooked into the protruding loop and the element can be transported safely.

PFEIFER

Bent Loop


BS Anchor System

Advantages:


- Safe lifting
- simple installation
- secure fastening in the reinforcement
- no additional reinforcement
- colour coding.

Material:

round strand rope, high strength, galvanized, Holding bracket, bare sheet steel



Product description



PFEIFER bent loops consist of a specially shaped holding bracket, a highquality rope and an appropriately marked load capacity identification tag. The holding bracket is intended for the correct alignment of the loop and for fixing to the reinforcement with wire or cable ties. The free ends are for anchoring in the concrete. In the cast in concrete state, the loop protrudes above the concrete surface and can be used for attachment when lifting or transporting the precast concrete element.

Table 1: Colour coding

Type/Size	Colour			
WS 4,0	emerald green			
WS 5,2	curry			

Safety

In defining safety, it is assumed that the lifting anchors are used in precast elements manufactured in a factory with continuous monitoring. In accordance with VDI/BV-BS 6205, the working coefficients are as follows:

- Full section failure:
- Steel rope failure:
- Concrete failure:
- Dynamic factor (load side):

γ _s	= 3,0
γ_{seil}	= 4,0
γ_{c}	= 2,1
ψ_{dyn}	= 1,3

Intended use






Figure 2







The PFEIFER bent loop is intended for the lifting and transport of plane precast units. In regular use the bent loops may be loaded straight or up to an angle of inclination of 30° from the perpendicular only in the direction of the free rope ends.

Instructions for installation and use

Intended use



Dimensioning




	.)[-,	0–30°	reinforce-	structural element		sion	tance from edge	from edge	distance	
		[kN]	ment	thickness	ü	е	C ₁	C ₂	S	
		\geq 15 N/mm ²		a ,			[mm]	[mm]		
_				[mm]	[mm]	[mm]			[mm]	_
	WS 4.0	40	2 x R257	200	120	170	450	450	900	
	WS 5.2	52	2 x R335	230	120	200	600	600	1200	_

Installation

Notice:

Installation only by trained expert personnel:

- use only original PFEIFER Bent Loops
- adhere to all installation rules
- fasten the Bent Loop in such a way that its position cannot change
- compact the concrete carefully, paying attention to the built-in components




Installation

Fixing the loop




- cable tie.

Incorrect use and discarding time





PFEIFER-Schachtabhebersystem SAS



Product description

The PFEIFER SAS System demonstrates the versatility of the PFEIFER lifting anchors. Proven PFEIFER lifting anchors in combination with a specially developed lifting loop form the basis of the SAS System, which is used for the lifting and movement of pipes and manhole elements. Like all PFEIFER Systems, safety is the utmost priority here and takes the form of a self-contained system developed in compliance with the VDI/BV-BS 6205 directive. The anchors consist of special-grade precision steel tubes with anchor bolt or anchor plate, while the lifting device consists of a flat material and high-strength screws, combined with a flexible steel wire rope.

🕂 Advantages


- efficient and flexible transport of manholes
- attachment bolt cannot be lost
- optimum range of products for all practically relevant applications
- original PFEIFER colour coding for handling without mix-ups

😃 Product range

- SAS Lifting Anchor for Manholes
- SAS Lifting Device
- Accessories

S Directives

- design and production of all SAS Manhole Lifting System components and installation instructions in compliance with the EC Machinery Directive
- all products conform to VDI/BV-BS 6205 and are thus CE-compliant
- safe work equipment as defined in health & safety legislation according to BetrSichV (Operational Safety Ordinance)



PFEIFER BS Anchor System



Product description

The PFEIFER BS Anchors are the ideal lifting anchors if heavy structural elements have to be transported inexpensively. Special heavy-duty anchors have already been realised with load-bearing capacities of up to 180 t. The BS Anchors consist of an oval-bent, high-strength quality steel rope, which is swaged with a special ferrule – with the experience of a rope making dynasty stretching back 436 years.

It is suitable for solid, compact structural elements as well as slender prestressed beams. The transport of bridge elements and raker beams for sports stadia is thus no problem. The additional use of a lifting and turning device can be dispensed with, since attachment is made directly to the suspension gear hook or shackle. The part of the PFEIFER BS Anchor that protrudes above the surface can be cut off directly after use. Associated system components with an optional recessed installation are the BS Hook and the BS Moulding Insert.

🕂 Advantages


- standard heavy duty anchor
- direct attachment to the suspension hook, without expensive lifting devices
- inexpensive alternative for the transport of precast elements
- original PFEIFER colour coding for handling without mix-ups
- wide range of applications already realised as a custom anchor up to 180 t



- BS Lifting Anchor up 180 t
- BS Lifting Device
- Accessories

§ Directives

- design and production of all BS Anchor System components and installation instructions in compliance with the EC Machinery Directive
- all products conform to VDI/BV-BS 6205 and are thus CE-compliant
- safe work equipment as defined in health & safety legislation according to BetrSichV (Operational Safety Ordinance)



PFEIFER Custom Lifting Anchor



Product description

The search for solutions to numerous problems leads customers to the PFEIFER Custom Lifting Anchors, such as the PFEIFER Lifting Box, which was developed for the safe transport of manhole elements, and the PFEIFER Bent Loop for the lifting and transport of concrete floors and angled elements. And that's not all – the PFEIFER LB Anchor, which serves as a lifting anchor for storey-high wall panels made of lightweight aggregate concrete, and the PFEIFER Masonry Anchor, which is pushed through the hollow space of the stones and grouted after completion of the brick element, are also so-called custom lifting anchors.

Advantages

- the solutions to customer problems the right anchor for every application
- economic alternatives for special applications
- experience in development and proven PFEIFER quality

😃 Product range


- PFEIFER Lifting Box
- PFEIFER Bent Loop
- PFEIFER LB Anchor
- PFEIFER Masonry Anchor

S Directives

- design and production of all custom anchor components and installation instructions in compliance with the EC Machinery Directive
- all products conform to VDI/BV-BS 6205 and are thus CE-compliant
- safe work equipment as defined in health & safety legislation according to BetrSichV (Operational Safety Ordinance)







Lifting Anchor Systems Thread System

Lifting Anchor Systems **BS** Anchor System

Lifting Anchor Systems WK Anchor System

Fixing Systems DB Anchor 682 for Permanent Fixing

Fixing Systems Socket Dowels **Polyamide Sockets**

Fixing Systems HK Assembly Anchor System

Connection Systems Column Shoe System Wall Shoe System

Connection Systems Stell Bearing Staircase Bearing VarioSonic

Connection Systems Sandwich Anchor System

Connection Systems Concrete Earthing System BEB

Reinforcement Systems VS®-Wire Rope Loop System

Reinforcement Systems PH Reinforcement Continuity System

Cable Tension Members Tension Rod System

Attachment Materials (Wire Ropes, Chains, Textiles)

Lashing Systems

Grabs for Reinforcing Steel **Balancing Spreader Beams**

This document is superseded when a new edition appears at www.pfeifer.info

Germany Headquarters

PFEIFER SEIL- UND HEBETECHNIK GMBH Dr.-Karl-Lenz-Straße 66 D-87700 MEMMINGEN Telefon +49(0)8331-937-312 Telefax +49(0)8331-937-342 E-Mail export-bt@pfeifer.de Internet www.pfeifer.info Lechstraße 21 D-90451 NÜRNBERG Tel. 0911-6427808 Fax 0911-6428472 E-Mail nuernberg-bt@pfeifer.de

Austria PFEIFER SEIL- UND HEBETECHNIK GMBH Dr.-Karl-Lenz-Straße 66

D-87700 MEMMINGEN Telefon +49(0)8331-937-211Telefax +49(0)8331-937-342E-Mail bautechnik@pfeifer.de

Denmark JORDAHL & PFEIFER Byggeteknik A/S Risgårdevej 66, DK-9640 Farsø Tel. +45-9863-1900 E-Mail info@jordahl-pfeifer.dk

France

ഗ

 \geq

0

 \vdash

 \triangleleft

C

0

_

Ω.

0

JORDAHL H-BAU France Siège, 7 rue des Vallières Sud 25220 Chalezeule Tél +33-3 81 25 04 65 Fax +33-3 81 25 07 96 E-Mail info@jordahl-hbau.fr

Spain

PFEIFER Cables y Equipos de Elevación, SLU. Avda. de los Pirineos, 25 – Nave 20 San Sebastián de los Reyes ES-28703 MADRID Tel. +34-916593185Fax. +34-916593139E-Mail p-es@pfeifer.de ES-08820 BARCELONA Tel./Fax +34-93-6364662Móvil +34-64-9154948E-Mail frieda@pfeifer.de

Russia 000 PFEIFER KANATI & PODJÖMNIE TEHNOLOGII RU-119017 MOSCOW Pyzhevskiy pereulok, h.5, bld. 1, office 108 Tel. +7-495-363-01-27 Fax +7-495-363-01-28 E-Mail info@pfeiferrussia.ru

Hungary PFEIFER GARANT KFT. Gyömröi út 128 HÚ-1103 BUDAPEST Tel. +36-1-2601014 Fax +36-1-2620927 E-Mail info@pfeifer-garant.hu

Singapore

J&P BUILDING SYSTEMS PTE LTD. No. 48 Toh Guan Road East #08-104 Enterprise Hub SG-SINGAPORE 608586 Tel. +65-6569-6131 Fax +65-6569-5286 E-Mail info@jnp.com.sg

UAE

EMIRATES GERMAN BUILDING MATERIALS TRADING (LLC) P.O. Box 18917 UAE-DUBAI Tel. +971-4-2676644 Fax +971-4-2676646 E-Mail info@emirategerman.com

Switzerland

Pfeifer Seil- und Hebetechnik GmbH Kurt Styger Gebietsverkaufsleitung Schweiz Bautechnik Dr.-Karl-Lenz-Strasse 66 D-87700 Memmingen Telefon: +41(0)797254931 Email: kstyger@pfeifer.de

United Kingdom

J&P BUILDING SYSTEMS LTD. Unit 5 Thame Forty Jane Morbey Road GB-THAME, OXON OX9 3RR Tel. +44-1844-215200 Fax +44-1844-263257 E-Mail enquiries@jp-uk.com

Czechia

JORDAHL & PFEIFER STAVEBNI TECHNIKA S.R.O. Bavorská 856/14 CZ-15500 PRAHA 5 Tel. +420-272700701Fax +420-272703737E-Mail info@jpcz.cz

Romania

S.C. JORDAHL & PFEIFER TEHNICĂ DE ANCORARE S.R.L Str. Malului Nr. 7, et.1 R0-550197 SIBIU JUD. SIBIU Tel. +40 269 246 098 Fax +40 269 246 099 E-Mail info@jordahl-pfeifer.ro

Poland

JORDAHL & PFEIFER TECHNIKA BUDOWLANA SP. Z 0.0. ul. Wrocławska 68 55-330 KRĘPICE k/ Wrocławia Tel. +48 71 39 68 264 Fax +48 71 39 68 105 E-Mail biuro@jordahl-pfeifer.pl

> 12.17 AB/MA 286498 Images: Fotolia